

JAYCE ? Sample Bill of Materials (reference only)

Project: Demo 40x60x14 Gable • ZIP 73533 • Sample data

Item	Qty	Unit	Notes

Primary frame columns	8	EA	Rigid frame
Primary frame rafters	8	EA	Rigid frame
Endwall columns	6	EA	Cold-formed
Sidewall girts	48	EA	Z / C section
Endwall girts	24	EA	Z / C section
Purlins	72	EA	Z section
Eave strut	4	EA	
Base angle	200	LF	
Wall panels (26 ga)	2,480	SF	Incl. waste factor
Roof panels (26 ga)	2,720	SF	Incl. waste factor
Wall screws	1,860	EA	
Roof screws	2,040	EA	
Closure strip	40	EA	
Trim ? eave	8	EA	Catalog
Trim ? rake	8	EA	Catalog
Trim ? base	8	EA	Catalog
Anchor bolts (ref)	?	?	By PE / foundation

Site criteria (sample): wind / snow / seismic from ZIP lookup

Steel weight (sample roll-up): see live BOM in Jayce for project totals

DISCLAIMER: Estimating and reference only. Not sealed engineering.

Have a licensed PE review and stamp before fabrication or construction.

<https://jaycesoftware.com/steel-building-bom>